

Mandatory Submission

Annex 2: Custom Booth Construction Safety Commitment Letter

Submission Deadline: October 6, 2026

Our construction company hereby undertakes full compliance with the *Fire Protection Law of the People's Republic of China*, National Electrical Equipment Safety Specifications, *Beijing Municipal Regulation for Large-Scale Mass Events*, hotel venue management rules and all other official industry standards throughout all construction phases. We uphold the core principles of "the builder bears full responsibility", "Safety First, Human-Oriented", and guarantee complete personal and property safety during all construction work:

1. All construction personnel will receive formal safety training, hold valid operation certificates, wear safety helmets on-site, and conduct construction safely. A dedicated on-site safety supervisor will be appointed for daily inspection and risk monitoring.
2. Full adherence to all hotel fire and safety rules: smoking is banned throughout hotel interiors. All construction teams must deploy portable fire extinguishers on-site. Booth structures must never block emergency exits, fire roller shutters, hydrants, fire ditches, sprinkler systems or evacuation signage. Flammable materials including paint, thinner and gasoline are prohibited; all open-flame operations are forbidden. All build materials must be eco-friendly and meet national flame-retardant standards.
3. Unauthorized tampering with hotel fixed electrical boxes, water supply and gas lines is prohibited. All electrical connections must follow national electrical safety codes: distribution boxes must include matching earth leakage protection and full earthing. Only double-sheathed insulated cables may be used, with fully enclosed terminal connections and zero exposed wiring.
4. All high-altitude work must be performed by certified specialists. All aerial lift operators must wear safety helmets and harnesses, conduct pre-operation hazard assessments, and secure equipment before work commences. Harness lanyards must be secured above operator height with ground spotters to restrict unauthorized personnel below work zones.
5. Certified electrical technicians must remain on-site for all exhibition open days, with all booth power fully shut down daily before venue closing.
6. Upon dismantling, all construction materials must be fully removed from hotel premises with zero residual waste left in loading zones or exterior venue areas.

 **Contractor Manager:** Mr. Guojun Li
 **Mobile:** +86 134 6976 9013
 **Email:** liguojun@medcircle.cn

Full detailed requirements are referenced in the Hotel Venue Safety & Management Regulations.

The authorized legal representative of our construction company confirms full reading and acknowledgment of this safety undertaking and all referenced venue regulations, and guarantees full compliance during move-in, dismantling and material transportation. Our company shall bear 100% legal and financial liability for all accidents (personal injury, fire, venue property damage) arising from rule violations, with no liability transfer to official service provider or event organizer.

Construction Company Official Seal: _____

Authorized Legal Representative Signature: _____

Contact Phone: + _____

Date: _____



 **Contractor Manager:** Mr. Guojun Li
 **Mobile:** +86 134 6976 9013
 **Email:** liguojun@medcircle.cn